

Operator: Patton Oil Co.

34-95-17W

NE SW SE A1

Webster #2

SEP 30 1985

DRILL STEM TESTS

(1.) Topeka
3258' to 3290'

IH	1678	
IF	56-89	30 minutes
ISI	858	30 minutes
FF	145-163	30 minutes
FSI	847	30 minutes
FH	1678	

State Geological Survey
WICHITA BRANCH

Anchor - 32 feet
Initial Blow - Fair, 6 inches
Final Blow - Fair, 6 inches
Recovery - 330 feet mud/oil show on top of tool

(2.) Toronto, Lansing "A"
3358' to 3380'

IH	1723	
IF	123-123	30 minutes
ISI	648	60 minutes
FF	123-123	30 minutes
FSI	626	60 minutes
FH	1720	

Anchor - 22 feet
Initial Blow - Weak, 4 inches
Final Blow - Weak, 1 inch
Recovery - 50 feet oil cut mud, 40% oil, 10% gas
60 feet oil spotted mud

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1985

CONSERVATION DIVISION
Wichita, Kansas

Webster #3

34-9-19W

(3.) Lansing "C-D"
3385' to 3420'

IH	1712
IF	112-112
ISI	134
FF	112-112
FSI	134
FH	1689

Anchor - 35 feet
 Initial Blow - Weak, 3 inches
 Final Blow - None
 Recovery - 60 feet oil cut mud, 20% oil
 60 feet oil cut mud, 15% oil

(4.) Lansing "E-F"
3420' to 3440'

IH	1756	
IF	100-100	30 minutes
ISI	168	30 minutes
FF	--	
FSI	--	
FH	1723	

SEP 30 1985

State Geological Survey
WICHITA BRANCH

Anchor - 20 feet
 Initial Blow - Weak, died in 4 minutes
 Recovery - 10 feet mud w/oil spots

(5.) Lansing "G"
3451' to 3461'

IH	1756	
IF	112-123	30 minutes
ISI	369	60 minutes
FF	190-213	30 minutes
FSI	369	60 minutes
FH	1745	

Anchor - 10 feet
 Initial Blow - Fair, 4 inches built to 8 inches
 Final Blow - Fair, 4 inches
 Recovery - 310 feet muddy water, no show oil

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1985

CONSERVATION DIVISION
Wichita, Kansas

(6.) Conglomerate Sand *Webster #2*
3625' to 3675' *34-9-19W*

IH 1901
IF 76-78
ISI 935
FF 134-145
FSI 924
FH 1890

Anchor - 50 feet
Initial Blow - Weak, 3 inches
Final Blow - Weak, surface, flushers tool
Recovery - 150 feet oil cut mud, 1% oil

(7.) Arbuckle
3683' to 3706'

IH 1991
IF 179-448
ISI 1046
FF 592-725
FSI 1035
FH 1924

Anchor - 23 feet
Initial Blow - Strong, off bottom bucket in 14 minutes
Final Blow - Strong, off bottom of bucket in 2 minutes
Recovery - 1620 feet water, no show oil

SEP 8 0 1925

State Geological Survey
WICHITA BRANCH

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1925

CONSERVATION DIVISION
Wichita, Kansas