

LOGICAL SOCIETY
8 East Murdock
Wichita, Kansas

OCT 3 1970

12-9-20W
(SE S NW
Elev. 2097

15-103-20312

DRILLERS LOG

COMPANY:
CONTRACTOR:
LEASE NAME:
LOCATION:

Hinkle Oil Co.
Aspen Drilling Co.
Lambert #1
SE-SE-NW Sec. 12-T9S-R20W

Rooks County, Kansas
2097 KB

ELEVATION:
SURFACE CASING:
COMMENCED:
COMPLETED:
ROTARY TOTAL DEPTH:

7 jts. (283') 8 5/8"
June 5, 1970
June 16, 1970
3647'

Dry/ark

FORMATION DEPTH

Surface clay, sand & shale 235
Shale 289
Shale & Sand 900
Shale 1050
Sand 1220
Red Bed 1548
Anhydrite 1590
Shale 1740
Shale & Shells 2345
Lime & Shale 2775
Shale & Lime 3170
Lime 3590
Arbuckle 3647

Ran 7 jts. (283') 8 5/8" casing set
at 289' with 200 sacks 60/40 Pozmix.
Cement did circulate.

DST #1 3231-3254
DST #2 3291-3345
DST #3 3346-3392 B.
DST #4 3440-3525
DST #5 3558-3590
DST #6 3590-3605
DST #7 3605-3647

Sample Top
Anhydrite 1548
Anhydrite 1590
Top of 3097
Klein 3283
Klein 3304
Klein 3323
Klein 3579
Arbuckle 3582

D & A

AFFIDAVIT

State of Kansas)
County of Barton) ss:

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

W.D. 10.

12-9-20W

No. 1 Lambert