

13-9-20W
NW SE NE

JUN 19 1971

DRILLERS LOG

Dry Park
15-1103-20325

COMPANY:
CONTRACTOR:
LEASE NAME:
LOCATION:

Aspen Resources, Ltd.
Aspen Drilling Co.
Steeple #1
NW-SE-NE Sec. 13-T9S-R20W
Rooks County, Kansas
2080 K. B.
6 jts. (242') 8 5/8"
October 10, 1970
October 20, 1970
3593'

ELEVATION:
SURFACE CASING:
COMMENCED:
COMPLETED:
ROTARY TOTAL DEPTH:

<u>FORMATION</u>	<u>DEPTH</u>
Surface Clay & Shale	120
Shale	1000
Sand	1245
Red Bed & Shale	1510
Anhydrite	1548
Shale & Shells	1950
Shale & Lime	2270
Lime & Shale	2675
Shale & Lime	3100
Lime & Shale	3262
Arbuckle	3568
Rotary Total Depth	3593

Ran 6 jts. (242') 8 5/8" casing
set at 249' w/150 sacks.
Cement circulated.

DST #1	3296-3320
DST #2	3320-3364
DST #3	3563-3568
DST #4 (mis-run)	3567-3573
DST #5	3563-3578
DST #6	3563-3588
DST #7	3563-3593

D & A

AFFIDAVIT

State of Kansas)
) ss:
County of Barton)

Log Logs
* *Arby* 1510
* *B. W.* 1548
Heebner 3256
Taronto 3277
Lancing 3293
Wea Ark 3562
Solid 3584
* *Drillers Log*

The undersigned, being duly sworn on oath, states that the above statement and log are a true and correct record and log of the well drilled at the location above described.

William S. Schachle
William S. Schachle, Affiant

Subscribed and sworn to before me this 23rd day of October, 1970.

Theora Holleman
Theora Holleman, Notary Public

My commission expires: April 18, 1972

