

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY

508 E. Murdock,

Wichita, Kansas

Company - PALMER OIL CORP. ET AL
 Farm - Miller No. 1

SEC. 18 T. 9 R. 20W
 SE SW SW

Total Depth. 3791

Comm. 3-31-51

Comp. 4-25-51


Shot or Treated.

Contractor. Musgrove Petro. Corp.

Issued. 7-7-51

County. Rooks

KANSAS



CASING:

8 5/8" 153' cem. w/110 sx.

5 1/2" 3778 1/2' cem. w/75 sx.

Elevation. 2239 R.B.

2237 (M)

Production. 116 bbls. Phys.

Figures Indicate Bottom of Formations.

shale & shells	153
shale	1075
shale & sand	1500
shale, shells & red	
bed	1730
shale	1751
anhyd.	1781
shale & shells	2245
shale & lime	2345
lime brkn	2410
shale & lime	2600
lime brkn	2630
shale & lime	3030
lime brkn	3130
lime & shale	3265
lime	3778
Arb. lime	3780 RTD
Arb. lime	3791
Total Depth	

Tops: R.B.

Heebner 3459

Toronto 3484

Lansing 3498

Base K.C. 3712

Congl. 3756

Simpson 3763

Arb. 3778

Acidized w/1000 gals. on 4-20-51