

23-9-20W

15-163-21198

CONTRACTOR'S WELL LOG

Survey

WICHITA, BRANCH

OPERATOR: **PI**
CONTRACTOR:
WELL NAME:
LOCATION:

SPUD DATE:
COMPLETION DATE:

Petro-Pak Corporation
Abercrombie Drilling, Inc.
STEEPLES #1
SE SE NW, Section 23-9S-20W
Rooks County, Kansas
1/26/81
2/02/81

0	290	Sand & Shale
290	616	Shale
616	1616	Sand & Shale
1616	3422	Shale
3422	3508	Shale & Lime
3508	3698	Lime
3698	3728	Shale & Lime
3728	3841	Lime
	3841	Rotary Total Depth

Spud hole @ 7:00 p.m., 1/26/81. Drilled 290' of a 12 1/4" hole. Ran 7 jts. of 8 5/8" - 20# casing, new (tally 279') Set @ 285'. Cemented with 200 sx. of common 2% gel, 3% c.c. Cement did circulate. Cement by Sun Cement. Plug was down @ 4:15 a.m., 1/27/81.

T.D. @ 3841'. Set 1st Plug @ 850' with 65 sx.; Set 2nd Plug @ 270' with 30 sx.; Set 3rd Plug @ 40' Solid Bridge with 10 sx. Rathole with 5 sx. Spotted heavy mud between plugs. 50-50 posmix, 6% gel. Job was completed @ 2:00 p.m., 2/02/81. State Plugger - Marion Schmidt.

STATE OF KANSAS)
) SS
COUNTY OF SELGWICK)

Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the STEEPLES #1, SE SE NW, Section 28-9S-20W, Rooks County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
Jack L. Partridge, Asst. Sec./Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 6th day of February, 1981.