

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-103-01763


Company- NADEL & GUSSMAN  
Farm- Marcotte No. 4

SEC. 26 T. 9 R. 20W  
SW SW SW

Total Depth. 3829  
Comm. 3-30-53 Comp. 4-10-53  
Shot or Treated.  
Contractor.  
Issued. 6-6-53

County Rooks

KANSAS



CASING:

10 3/4 124' w/ 100 sx cement  
7 in. 3824' w/ 100 sx cement

Elevation. 2262

2265 (3)

Production. Pot. 3000 BO, No water

Figures Indicate Bottom of Formations.

surface	124
shale, shells & sand	1000
shale & sand	1500
shale & shells	1736
anhydrite	1773
shale & shells	2010
shale & lime	2350
shale & broken lime	2425
shale & lime	2689
lime	3720
lime & shale	3772
lime & conglomerate	3817
shale	3823
dolomite	3829
Total Depth	

GEOLOGICAL TOPS:

Anhydrite	1736
Heebner shale	3482
Toronto lime	3506
Lansing KC	3522
Conglomerate	3776
Simpson	3800
Arbuckle	3823

Drilled plug. Filled up 1000' oil  
in 20 min. 2600' oil - total fillup.  
SWBD. 85 BO per hr. for 4 hrs.  
1700' of bottom.