

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-163-00444

Company- LEE PHILLIPS OIL CO.
 Farm- Steeples No. 1

SEC. 26 T. 9 R. 20W
 SE SE NE

Total Depth. 3767
 Comm. 11-12-52 Comp. 11-23-52
 Shot or Treated.
 Contractor.
 Issued. 12-13-52

County Rocks
 KANSAS



CASING:
 8 5/8" 252' cem. w/150 sx.

Elevation. 2206 K.B.

Production.

2205 2nd
 Dry

Figures indicate Bottom of Formations.

clay, sand, & shale	60
shale & shells	257
shale	480
shale & sand strks	890
sand	1020
shale	1065
sand, shale & shells	1165
sand	1370
red bed	1490
shale & red bed	1643
anhyd.	1688
shale & shells	2355
shale & lime	2450
shale & shells	2610
lime & shale	2935
lime	3050
lime & shale	3455
lime	3642
lime & shale	3687
lime, chert & shale	3727
lime & shale	3748
lime	3767
Total Depth	

Tops:	
Topoka	3242
Heebner	3410
Toronto	3430
Lansing	3451
Base Kansas City	3664
Conglomerate	3695
Arbuckle	3647

D.S.T. 3517-3539 open 20 mins. rec.
 630' salt wtr, Bkt 1340#.
 3594-3605 open 20 mins., rec. 4' mud.
 BHP 0 1/2.