

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-163-00055

Company. NADEL & GUSSMAN
Farm- Hinkhouse

No. 19

SEC. 27 T. 9
NW SE SW

R. 20W

Total Depth. 3812

Comm. 3-4-54

Comp. 3-15-54


Shot or Treated.

Contractor.

Issued. 5-22-54

County Rooks

KANSAS



CASING:

10 3/4" 145' w/100 sx com.
7" 3811' w/150 sx com.

Elevation. 2266

Production. 454 BO/no wtr

Figures Indicate Bottom of Formations.

red bed-sand	150
shale	795
sand	1090
shale	1150
sand	1430
shale-red vod	1700
shale-shells	1752
anhydrite	1792
shale-shells	2010
shale-brkn lime	2210
shale-lime	3527
lime	3679
lime-shale	3757
conglomerate	3804
Simpson shale	3810
Arbuckle	3812
Total Depth	

TOPS:

Hoebner	3470
Lansing-Kansas	
City	3510
Base Kansas City	3731
Conglomerate	3757
Simpson shale	3804
Arbuckle	3810

Perf. 24 holes 3596-
3600. Swab 2 1/2 BOPH Nat.
500 gal. acid
Swabb 44 BOPH/4 hrs.
Grav. 25 at 60 degree.