

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas


15-1103-00736

Company- RESERVE DRILLING COMPANY
Farm- Lena Graham No. 1

SEC. 29 T. 9 R. 20W
NW SE NW

Total Depth. 3866'
Comm. 8-2-58 Comp. 8-11-58
Shot or Treated.
Contractor. Reserve Drilg. Co.
Issued. 11-22-58

County Rocks KANSAS



Elevation. 2281 RB

Production. 100 BOPD HHY POT

CASING:

8 5/8" 199' w/125 sx. cem.
5 1/2" 3861' w/ 75 sx. cem.

Figures indicate Bottom of Formations.

shale and sand	202
shale and shells	745
shale and sand	990
sand	1200
shale and sand	1505
shale and red bed	1765
shale and shells	1780
anhydrite	1835
shale and shells	2300
lime and shale	2380
sandy lime and shale	2500
lime and shale	3470
lime	3866
Total Depth	

GEOLOGICAL TOPS

Anhydrite (Scout)	1780
Heebner	3525
Toronto	3547
Lansing	3565
Base Kansas City	3774
Conglomerate	3837
Arbuckle	3860