



Farmer Oil Well Service, Inc.

1614 East 29th St.

Hays, Kansas 67601

Blond Farmer, President

(913) 625-5728

Sam Farmer, Vice President

February 2, 1982

Wamego Oil, Inc.
Lambert #1
900' FNL, 990' FEL
SE/4 of Sec. 29-98-20W
Rooks County, Kansas

OPERATOR:

WAMEGO OIL, INC.
MANHATTAN, KS

CONTRACTOR:

PIONEER DRILLING
PLAINVILLE, KS

Spud Date: January 27, 1982
Set 243', 8 5/8" casing
Completed: January 27, 1982
Completed: D&A, February 2, 1982

CREW:

Rig #2

Toolpusher: Sanders
Drillers: Sanders
Dinkel
Acheson

ELEVATION:

Laughlin-Simmons & Company
Hays, Kansas

Ground Level 2284
Kelly Bushing 2289

All measurements shown are from Rotary Bushing.

SAMPLES:

Ten foot intervals from 3200 to 3880, and five foot intervals from 3880 to 3920 R.T.D.

DRILLING TIME:

One foot intervals from 3200 to 3920 R.T.D.
A copy of the drilling time is included with this report.

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1982

CONSERVATION DIVISION
Wichita Kansas

FORMATION TOPS:

02394

29-9-20w

Sample Tops

Top Anhydrite	1776 (+513)
Base Anhydrite	1818 (+471)
Topeka	3331 (-1042)
Heebner	3539 (-1250)
Toronto	3562 (-1273)
Lansing K.C.	3580 (-1291)
Base K.C.	3806 (-1517)
Conglomert	3866 (-1577)
Reworked Arbuckle	3900 (-1611)
RTD	3920 (-1631)

SAMPLE DESCRIPTION: ALL MEASUREMENTS TAKEN FROM DRILLING TIME LOG

3600-04	Limestone, white to light gray, fossiliferous, fine crystalline, light stain, no free oil or odor, rocks were tight. This zone is of no commercial interest.
3624-28	Limestone, white to tan, fossiliferous, oolitic to fine crystalline, light stain, some staining of dead, heavy oil, no free oil or odor, formation was tight. This zone is of no commercial interest.
3664-70	Limestone, white, fossiliferous, medium to fine crystalline, slight stain of heavy, dead oil, no free oil or odor. This zone is of no commercial interest.
3750-54	Limestone, white to gray, medium to fine crystalline, tight scattered staining of heavy, dead oil, no free oil or odor. This zone is of no commercial interest.
3762-66	Limestone, white, fossiliferous, medium to fine crystalline, light stain of oil, no free oil or odor, formation was tight. This zone is of no commercial interest.
3900-06	Weathered, reworked dolomite, mixed with red shale and red, yellow and white chert, stain of heavy, dead oil, no free oil or odor. This zone is of no commercial value.
3916-14	Weathered, reworked dolomite mixed with red shale and red, yellow and white chert, stain of heavy, dead oil, no free oil or odor. This zone is of no commercial value.

REMARKS:

The Lambert #1, 900' FNL, 990' FEL, SE/4 of S 29-9S-20W in Rooks County, Kansas ran structure equal to the Kern "D" #1, SE-SW-NW Sec: 29-9S-20W in Rooks County, Kansas throughout the upper Kan. City. The Lambert started to thicken and by the top of the Kansas City the Lambert was running 7' low to the Kern "D" #1. Good clean Arbuckle was never attained on the Lambert #1 by a (-1611) which made the Lambert 12' low to the Kern "D" #1 at that point. The decision was made to abandon test.

Respectfully submitted,



Blond Farmer