

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - CONTINENTAL OIL CO.
Farm - K. R. Hinkhouse No. 1.

15-163-04034

SEC. 32 T. 9 R. 20 W
NE SE SE
990' N 330' W SE cor.

Total Depth. 3847'
Comm. 5-10-44 Comp. 5-24-44
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 10-28-44

County. _____
Rocks
KANSAS



CASING:
10^{3/4}" 237' Cem.
6" 3847' Cem.

Elevation. _____

Production. Pmp Pot. 480 B.
30 BW

Figures Indicate Bottom of Formations.

sand & shale	0-40
shale & shells	870
sand & shells	1375
sand	1540
shale & shells	1752
anhydrite	1800
shale & shells	2350
lime brkn & shale	2430
shale & shells	2600
lime	2685
lime brkn & shale	2775
lime & shale	2860
lime brkn & shale	2943
lime	3161
lime brkn	3242
lime	3835
Congl lime	3843
lime	3847
Total Depth	

Top of Arbuckle Lime 3840

5-31-44 Drilled out cem plug & hole filled 1669' w/oil in 9 hrs.
6-1-44 Perforated 6"OD casing w/23 shots fr 3840' to 3845' w/Lane-Wells gun perforator. Hole filled to 1975' w/oil in 7 hrs.
Swabbed 20 bbls. oil per hr off btm
8-22-44 Established a 24 hr physical pot. of 480 bbls. oil & 30 bbls. wtr

Total Depth 3847 in Arbuckle Lime

Note: Above footage calculated fr pumping DF, except form.