


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CONTINENTAL OIL CO.
Farm - E. Marcotte No. 1.

SEC. 33 T. 9 R. 20 W
SWc SW
330'N 330'E of SW cor

Total Depth. 3844 DFL 3843
Comm. 7-29-44 Comp. 8-29-44
Shot or Treated.
Contractor.
Issued. 2-17-45

County. Rooks
KANSAS



CASING:

10 3/4" 239' Cem.
6" 3839' Cem.

Elevation. _____

Production. Pot 25 B Min.
Temp. Swb.

Figures Indicate Bottom of Formations.

surface soil & sand 0-120
sand & shale 400
shale & shells 850
sand, shells & shale 1260
sand 1455
sand & shale 1650
red bed & shale 1740
anhydrite 1803
red bed & shells 1866
shale & shells 2170
lime & shale 2635
lime brkn & shale 2895
lime 3050
lime brkn & shale 3340
lime 3844
Total Depth DFL 3843

Top Arbuckle Lime 3838

8-28-44 Drilled out plug-
hole filled 2800'w/oil
in 6 hrs

8-29-44 Swbd 212 BO in
2 1/2 hrs @ 2000' off bottom

8-29-44 Estb 25 B min.
temp. swb. pot

T.D. 3843 in Arb. Lime

Note: Footages are from
pumping derrick floor
level, except formations.