

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- I.O. MILLER
Farm- Pywell "B"

No. 5
(Twin to #1)

15-163-07326
SEC. 35 T. 9 R. 20W
100' E of SE SW NE

Total Depth. 3795'

Comm. 11-10-55


Comp. 11-21-55

Shot or Treated.

Contractor. Virginia Drlg. Co. Inc.

Issued. 5-18-57

County Rooks
KANSAS



CASING:

Elevation. 2253 RB

8 5/8" 206 w/125 sx cem.
5 1/2" 3788 1/2'

Production. 243 bbls.

Figures indicate Bottom of Formations.

clay-sand-shale	110
shale shells	206
shale	525
shale-sand	825
shale shells	1105
sand	1130
shale-sand	1350
shale shells	1595
shale shells-red rock	1590
anhydrite	1735
lime-shale	1750
shale lime shells	1850
shale shells	1900
shale-lime	2040
shale shells	2280
lime-shale	2505
lime brkn	2640
shale-lime shells	2765
lime-shale	2775
lime	2945
lime-shale	3080
lime	3163
lime-shale	3270
lime	3315
lime-shale	3345
lime	3795

Total Depth

TOPS:

Heebner	3455
Toronto	3478
Lansing	3495
B/Kansas City	3702
Conglomerate	3738
Simpson	3772
Arbuckle	3787

DST #1 - 3528-65' Open 1 hr.,
Rec. 898' oil. IFP 80#, FFP 250#,
BHSIP 1050# in 15 min.

DST #2 - 3572-82' Open 1 hr.,
Rec. 1240' SW w/slight show
of oil throughout. IFP 0#,
FFP 640#, BHSIP 1195# in 15
min.

DST #3 - 3607-55' Open 1 hr.,
Rec. 293' SW, slight scum of
oil, FFP 0#, FFP 200#, BHSIP
1000# in 15 min.,

DST #4 - 3659-95' Open 1 hr.,
Rec. 400' of gas & 90' of very
heavy oil & gas cut mud. BHSIP 575# in
15 min.