

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company. R.W. SHIELDS
 Farm- Tremblay

No. 1

SEC. 3 T. 9 R. 21W
 NW NW NE

Total Depth. 3755'

Comm. 4-18-55

Comp. 4-28-55


Shot or Treated.

Contractor. Empire Drilg. Co.

Issued. 6-18-55

County Graham

KANSAS



Elevation. 2132 KB

Production. 73 BOPD

CASING:

8 5/8" 170' w/115 sx cem.

5 1/2" 3760' w/125 sx cem.

Figures indicate Bottom of Formations.

shale-shells	970
sand-shale-shells	1140
shale-shells	1600
Anhydrite	1637
shale-shells	2797
lime-shale	3380
lime	3558
lime-shale	3639
Conglomerate	3674
shale-lime	3748
lime	3755
Total Depth	RTD

TOPS:

Anhydrite	1600
Heebner	3286
Lansing-Kansas City	3327
B/Kansas City(SC.)	3545
Conglomerate Sc.	3667
Eroded Arbuckle Sc.	3710
Sol. Arbuckle Sc.	3725

CABLE TOOL RECORD:

Perf. 20 shots 3667'-3672'
 Acidized w/100 gals., swabbed
 1 1/4 bbls oil per hr.—no wtr.

DST #1 - 3320-45 KB

Open 1 hr. Weak blow
 throughout test. Shut in 15 min.
 Rec. 25' slightly oil & gas cut
 mud, 60' slightly oil & gas cut
 muddy wtr. BHP 1200#.

DST. #2 - 3667-74 KB

Open 1 1/2 hrs. Weak in-
 creasing to stron blow throughout
 test. Shut in 20 min. Rec. 360' oil.
 BHP 830# FFP 120#