


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CONTINENTAL OIL CO.
Farm - E. Clack No. 2.

SEC. 10 T. 9 R. 21 W
S Eo SW
3 30' N 330' W S $\frac{1}{4}$ Cor.

Total Depth. 3688' CPL 3685'
Comm. 2-7-44 Comp. 3-31-44
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 8-12-44

County. Graham
KANSAS



CASING:
10 $\frac{3}{4}$ " 239' Cem.
6" 3662' Cem.

Elevation. _____

Production. Phy. Pot. 812 B.

Figures Indicate Bottom of Formations.

surface soil	80
shale	718
sand & shells	1210
sand & shale	1550
shale	1640
anhydrite	1685
shale & shells	2200
lime & shale	2460
lime	2580
lime & shale	2670
lime brkn	2755
lime	2830
lime brkn	2975
lime	3013
lime brkn	3080
shale	3120
lime brkn & shale	3260
lime	3295
shale	3305
lime	3663
chert	3665
lime	3688
Total Depth.	

Top of Arbuckle Lime 3660

3-29-44- Drilled shoe & hole
filled 2800' w/oil in 10
hrs. Deepened to 3658, and
swbbed 14 BOFH for 3 hrs..
4-9-44- Acidized through 2" tbg
w/1,000 gals
4-18-44- Established 24 hr phy.
pot. of 812 Bbls oil
Total Depth 3685' in Arb. Lime.
Note: Footages frm cement flr
level except formations.