


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CONTINENTAL OIL COMPANY
 Farm- E. Clack "A" No. 3

SEC. 10 T. 9 R. 21W
 SE NW SW
 1650' fr S & 990' fr W of Sec.

County Graham KANSAS

Total Depth. 3672' RTD 3674' CTTD
 Comm. 5-4-56 Comp. 5-12-56
 Shot or Treated.
 Contractor. Lohmann-Johnson Drilling Company, Incorporated
 Issued. 4-20-57



Elevation. 2190' RB

Production. 25 Bbls
 (Daily Allowable)

CASING:

8 5/8" 262' w/150 sx cem.
 5 1/2" 3269' w/150 sx cem.
 2 7/8" 3653'

Figures Indicate Bottom of Formations.

surface	263
shale	680
sandy shale	800
shale & shells	1055
Anhydrite	1696
shale	2020
shale & shells	2046
shale & lime	
streaks	2180
lime & shale	3370
shale	3455
lime & shale	3672 RTD
lime & shale	3674 CTTD
Total Depth	

TOPS
 Heebner 3325
 Lansing 3365
 Arbuckle 3667

Producing Sand
 Arbuckle 3669-3674'

Remarks

DCleaned ou to 3672' 200'
 of oil in hole in 30 min.
 Swabbed 42 bbls. of oil
 and no water in 4 hrs.
 Deepened to TD 3674'
 in Arbuckle Lime. Swabbed
 127 bbls of oil and no
 water in 7 hours, 300'
 off bottom. Established
 a State Pumping Potential
 of 476 bbls of oil and
 no water in 24 hrs.
 Daily allowable 25 bbls.