

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 065 — 20777
County Number

Operator

Continental Oil Company

Address

3535 N.W. 58th Street, Oklahoma City, Oklahoma 73112

Well No.

7

Lease Name

J. F. Loveridge

Footage Location.

1,980 feet from ~~XXX~~ (S) line 2,310 feet from (E) ~~XXX~~ line

Principal Contractor

C & G Drilling Co.

Geologist

Lewis O. Chubb

Spud Date

9-3-75

Total Depth

3,734'

P.B.T.D.

3,720'

Date Completed

9-29-75


Oil Purchaser

Mobil

S. 10 T. 9S R. 21 W

Loc. W/2 NW SE

County Graham

640 Acres
N

Locate well correctly

Elev.: Gr. 2,200'

DF ----- KB 2,205'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8	24	279'	Class H	180	3% gel 3% CaCl
Production	8 7/8"	5 1/2	14 & 15.5	3,733'	Class A	250	10% Salt 3/4% CFR-2

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
	None				

TUBING RECORD

Size	Setting depth	Packer set at			
2 7/8"	3,715'	-----	4	2 jets & 2 bullets	3662-68', 3673-77' 3686-90'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
100 gals. MCA mud acid	3662-90'
250 gals. MCA mud acid	3668-90'
500 gals. MCA mud acid	3662-77'

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
9-29-75		Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	49	bbls.	----- MCF	151	bbls. ----- CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
-----			3662-90'		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Continental Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 7	Lease Name J. F. Loveridge	Oil
S <u>10</u> T <u>9S</u> R <u>21</u> ^W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			Anhydrite	1675
			Heebner	3326
			Toronto	3348
			Lansing	3363
			Base LKC	3583
			Marmaton 1m	3612
			Arbuckle	3762

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature Engineer Title October 14, 1975 Date
---------------	--

