

W E L L L O G

10-9-21W
W/2 NW-SE
15-065-20777

OPERATOR: C-G DRILLING CO.

WELL NAME: LOVERIDGE #7 LOCATION: 1980' FR/SO LINE, 2310' FR.

COUNTY: GRAHAM STATE: EAST LINE KANSAS

WELL COMMENCED: SEPT 3, 1975 WELL COMPLETED: SEPT 11, 1975

ELEVATION: GL 2200' - RB 2205' TOTAL DEPTH: 3734'

PRODUCTION: PRODUCING RIG NO: 1

CASING - 8-5/8": SET @ 279' (7 JTS) W/180 SX COMMON 72% GEL 7 3% CA CL

5-1/2": SET 11' OB @ 3733'. RAN 3734.40' (116 JTS) NEW & USED
15 1/2# & 14# W/250 SX COMMON CEM 10% SALT 3/4% OF 1%
of CRF2.

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION	REMARKS:
			FROM VERTICAL	
0	880	SHALE & SAND	1/2° @ 700'	
880	1010	SAND		
1010	1090	SHALE & SAND		
1090	1165	SHALE		
1165	1395	SAND & SHALE	1° @1200'	
1395	1675	SHALE & RED BED		
1675	1705	ANHYDRITE		
1705	1925	SHALE	2° @1790'	
1925	2165	SHALE & SHELLS		
2165	2235	SHALE & LIME		
2235	3455	LIME & SHALE	1/4° @2473'	
3455	3673	LIME		
3673	3734	ARBUCKLE		DST #1 3644'-3673'
	3734	RTD		15-15-60-60 REC 150'
				HOCM IBHP 47## FBHP 463#
				IFP 44# FFP 80#

RECEIVED
OCT 16 1975

STATE OF KANSAS
COUNTY OF SEDGWICK

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.