


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

BARNSDALL OIL CO.
Evila Davignon No. 1

SEC. 11 T. 9 R. 21 W.
CSW SW

Total Depth 3762 DF
Comm. 8-19-42 Comp. 9-17-42
Shot or Treated.
Contractor. The Parker Drilling Co.
Issued. 10-10-42

County Graham



CASING.

103/4"
7"

279'36
3736'

cemented.
cemented.

Elevation.

Production. Pot. 761 B.
Phy.

Figures Indicate Bottom of Formations.

surface clay	35
sand	45
shale	245
shale and shells	846
sand	955
shale and sand	1060
red bed and sand	1215
shale and sand	1400
shale and shells	1720
anhydrite	1765
shale and shells	2075
shale	2205
shale and lime	2320
broken lime	2365
shale and lime St.	2425
lime	2435
broken lime	2460
lime and shale	2550
lime	2575
lime and shale	2590
shale and lime shells	2710
lime and shale	2780
lime	2800
shale and lime	2990
shale and lime shells	3020
broken lime & shale	3060
broken lime & shale streaks	3120
lime broken	3360
lime	3394
lime broken	3430
lime	3688
conglomerate	3710
conglomerate & lime streaks	3735
cherty lime	3740
Arbuckle lime	3762DF.

Total Depth.

Top Arbuckle lime 3736.35

9-18-42 283 bbls oil, no water, pumping 15 hours after 3000 gal acid
9-19-42 143 bbls oil, no water, pumping 8 hours.
9-24-42 340 bbls oil, no water, Pumping 17 Hrs (Phy.Pot.761 B.)