

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION CO.

Farm- Senesac

No. 1

SEC. 12 T. 9 R. 21W

NE NE NE

Total Depth. 3767'

Comm. 7-29-57

Comp. 8-11-57


County Graham

KANSAS

Shot or Treated.

Contractor. Shelley-Miller Drilg. Co.

Issued. 7-12-58



CASING:

8 5/8" 216' cem w/150 sx.

Elevation. 2147' RB

Production. Dry

Figures Indicate Bottom of Formations.

All meas. from top of RB.

post rock, clay & shale	200
shale & shells	216
shale	825
shale & shells	1430
red bed & shale	1647
Anhydrite	1687
shale & shells	2375
lime & shale	3060
lime	3766 RTD
lime	3767
Total Depth	

TOPS:

Topeka	3154
Heebner	3360
Lansing	3382
Base Kansas City	3620
Conglomerate	3678
Arbuckle	3720

DST #1 3468-86, 1 hr, SI 20", wk bc fr
blow thruout, rec. 120' HOCM, 30' MW -
BHP 940#, FP 30-90#

DST #2 3666-3715, op 1 hr, SI 20", rec. 12'
mud, sli oil specked. FPO, BHP 0.

DST #3 3748-54, 1 hr, SI 20", Rec. 50'
mud, 910# BHP.

DST #4 3723-34, 1 hr, SI 20", rec. 5'
mud, BHP 890#, FP 0.