

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
J. F. Loveridge No. 1.

SEC. 10 T.9 R.21W
CWL SE
1320' N 440'E S $\frac{1}{4}$ Cor.

County. Graham



* Total Depth. 3710'
Comm. 3-28-40 Comp. 4-19-40
Shot or Treated. 2000 Gals. Acid
Contractor. Parker Drlg. Co.
Issued. 8-3-40

CASING:
13 3/8" 262'
9 5/8" 1528'
7" 3673'

Elevation.

Production. Pot. 956 B.
No wtr

Figures Indicate Bottom of Formations.

surface	40
clay yellow	175
shale & shells	268
gumbo	310
shale blue & shells	495
shale & shells	650
sand	885
sand, shale, shells	1075
shale & shells	1637
red rock & shells	1657
anhydrite	1695
red bed, shale, shells	1905
shale & lime shells	2080
shale, lime shells, red bed	2160
shale & shells	2190
limo	2260
shale & lime	2530
limo brkn	2680
shale & shells	2780
shale & lime shells	2870
shale & shells	3075
shale & lime	3185
limo	3230
limo brkn	3330
limo	3435
shale & lime	3485
limo	3553
limo soft	3555
limo	3585
shale & limo	3610
conglomerate	3650
shale & limo	3673
dolomite	3690
limo	3710
Total Depth.	

Total Depth from cement floor
level 3709

Top of Arbuckle lime from
cement floor level 3671

Total fillup w/oil 2100'

Pumped 139 BO in 4 Hrs & 40
min. & pumped off.

5-1-40 acidized w/2000 Gals.

5-2-40 on initial potential

test the well pumped 318.65 BO
in 8 hrs giving the well a 24-hr
potential of 956 BO, no wtr