

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **SINCLAIR OIL & GAS**

SEC. 13 T. 9 R. 21W

FARM **Armand Brault** NO. **3**

LOC. **NW SW SW**
1060' FSL & 150' FWL of SW/4

TOTAL DEPTH **4240**

COMM. **4-28-67**

COMP. **5-9-67**

SHOT OR TREATED

CONTRACTOR **C & G Drlg.**

ISSUED **7-1-67**

COUNTY **Graham**

KANSAS

CASING

20 10
 15 8 5/8" @ 270' w/200 SX
 12 6
 13 5 1/2" @ 3810.28' w/350 SX

ELEVATION **2203' GL**

PRODUCTION **SWDW-RATE 0 K**
ARB-REAG 3805-4240

FIGURES INDICATE BOTTOM OF FORMATIONS

CASING - 8-5/8": SET @ 270' (9 its) W/200 SX COMMON CEMENT. + 2% CA. CL.

5-1/2": SET 116 its 3810.28 15 1/2# 3805 GL W/350 SX CEMENT
2 STAGE 1736 to SURFACE W/425 SX TRINITY LIGHT WEIGHT
+ 15% SALT

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
270	1157	SHALE	550 3/4°	
1157	1365	SAND	1000 1°	
1365	1718	SHALE & RED BED	1140 1°	
1718	1759	ANHYDRITE	1410 1-3/4°	
1759	1980	SHALE & SHELLS	1500 1-3/4°	
1980	2410	LIME & SHALE	1770 1-1/4°	
2410	2545	LIME	2050 1°	
2545	3480	LIME & SHALE	2650 1-1/4°	
3480	3770	LIME	3000 1°	
3770	4239	ARBUCKLE	3543 3/4°	
			4239 3/4°	

TOPS: SCOUT

Heebner 3388
 Toronto 3410
 Lansing 3427
 Conglomerate 3683
 Arbuckle 3739
 Reagan Sand 4213
 Granite 4232

STATE OF KANSAS
 COUNTY OF SEDGWICK) SS: