

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 065 — 20652
County Number

Operator

DANE G. HANSEN TRUST

Address

LOGAN, KANSAS 67646

Well No.

10

Lease Name

EICHMAN

Footage Location

660

feet from (N) ☒ line

660

feet from (E) ☒ line

Principal Contractor

C-G DRILLING CO.

Geologist

FRANCIS C WHISLER

Spud Date

JAN 27, 1974

Total Depth

3684

P.B.T.D.

Date Completed

FEB 4, 1974

Oil Purchaser

Mobil


S. 13 T. 9 R. 21 W^E_W

Loc. C N/2

County GRAHAM

640 Acres

N



Elev.: Gr.

DF KB 2152

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/4"	8 5/8"	28#	205.98'	Cement	150	2% Gel 3% C C
PRODUCTION		5 1/2"	14#	3672'	Salt Sat	125	
	2 Stagged			1644 to surface with	375 sacks		
	pozmix / 4% Gel						

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD				NONE	
Size	Setting depth	Packer set at			
2 1/2"	3660'				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
NONE	

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
3/1/74	Pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	60 bbls.	0 MCF	0 bbls.	0	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
			Arbuckle 3672-84		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

C-G DRILLING CO.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

OIL

Well No.

10

Lease Name

EICHMAN

s 13 0S R21W^E_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SHALE	0	370		
SHALE & SAND	370	685		
RED BED & SHALE	685	810		
DAKOTA SAND	810	870		
RED BED	870	1095		
SAND	1095	1290		
SAND & SHALE	1290	1653		
ANHYDRITE	1643	1683		
SHALE	1693	1955		
LIME & SHALE	1955	3290		
LIME	3290	3684		
ARBUCKLE & TOTAL DEPTH		3684		
DST #1 3450'-3475' OPEN 30 SI 30 OPEN 30 SI 45 REC 420' MUDDY SALT WATER IFP 162# FFP 226# DST #2 3550'-3590' OPEN 30 SI 30 OPEN 30 SI 45 REC 100' OIL & GAS CUT MUD IBHP 1165# FBHP 1165# IFP 36# FFP 81# DST #3 3633'-3655 OPEN 30 SI 30 OPEN 30 SI 30 REC 20' MUD IBH 27# FBHP 22# FFP 18# IFP 18# DST #4 3672'-84' OPEN 30 SI 30 OPEN 30 SI 45 REC 2500' OIL IBHP 1127# FBHP 1128# IFP 542# FFP 1119#				
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

*Phyllis Buchanan*

Signature Phyllis Buchanan

Office Manager

Title

February 15, 1974

Date