

State Geological Survey

KANSAS DRILLERS LOG

WICHITA, BRANCH

API No. 15 — 065 — 20,691
County Number

Operator
DANE G HANSEN TRUST

Address
LOGAN, KANSAS 67646

Well No. 11 Lease Name EICHMAN

Footage Location
330 feet from (N) ~~XX~~ line 660 feet from (X) (W) line

Principal Contractor C-G DRILLING CO. Geologist FRANCIS WHISLER


Spud Date AUGUST 17, 1974 Total Depth 3668 P.B.T.D.

Date Completed AUGUST 24, 1974 Oil Purchaser Mobil

S. 13 T. 9S R. 21W^E

Loc. N/2 N/2 N/2

County GRAHAM



Locate well correctly

Elev.: Gr.

DF KB 2146

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/4"	8 5/8"	20#	216.75'	COMMON	150	2% GEL 3% CA CL
PRODUCTION		5 1/2"	14#	3664'	COMMON	125	
2 STAGED TO TOP			FROM	1642'	60-50 POZMIX	375	6% GEL

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
				None	

TUBING RECORD

Size	Setting depth	Packer set at
2 1/2	3663	

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production 10/18/74		Producing method (flowing, pumping, gas lift, etc.) Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 53 bbls.	Gas XX MCF	Water 10 bbls.	Gas-oil ratio XX CFPB	
Disposition of gas (vented, used on lease or sold) XX			Producing interval (s) Open hole		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

DANE G HANSEN TRUST

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

OIL

Well No.

11

Lease Name

EICHMAN

S 13 T9S R21W^E_W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
SHALE		790	Anhydrite	1642
SAND	790	865	Heebner	3343
RED BED & SHALE	865	1150	Toronto	3365
SAND	1150	1375	Lansing	3383
RED BED	1375	1639	B/KC	3596
SHALE	1639	1642	Simpson Sh.	3649
ANHYDRITE	1642	1682	Arbuckle Dol.	3662
SHALE	1683	2120		
LIME	2120	2700		
LIME & SHALE	2700	3015	No Log	
LIME	3015	3665		
ARBUCKLE	3665	3668		

DST #1 3443'-3465'

OPEN 30 SI 30 OPEN 30 SI 45

REC 210' MUDDY WATER

IBHP 469# FBHP 469# IFP 67# FFP 123#

DST #2 3523'-3575'

OPEN 30 SI 30 OPEN 30 SI 45

REC 66' MUDDY WATER

IBHP 713# FBHP 847#

IFP 56# FFP 67#

DST #3 3664'-3668'

OPEN 30 SI 20 OPEN 30 SI 30

STRONG BLOW. REC 2010' FREE OIL

IBHP 1113# FBHP 1136# IFP 536#

FFP 802#

STATE OF KANSAS)
COUNTY OF SEDGWICK) ssSubscribed and sworn to before me this
4th day of September, 1974

My commission expires 12/7/74

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Notary Public

Signature G. F. Galloway

Partner

Title

9/4/74

Date

