

## WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 E. Murdock


Wichita, Kansas

Company **BARBAR DRILLING COMPANY**  
 Farm **Brault** No. **1**

SEC. 14 T. 9 R. 21W  
 SW SE SE

Total Depth. 3765  
 Comm. 6-17-48 Comp. 7-7-48  
 Shot or Treated.  
 Contractor.  
 Issued. 4-15-50

County. Graham  
 KANSAS



CASING:  
 10 3/4" 90' cem w/ 45 sx.  
 5 1/2" 3763' cem w/100sx.

Elevation. 2258 *Ind*

Production. 8 Bbbls.

Figures Indicate Bottom of Formations.

|                        |      |
|------------------------|------|
| Surface clay           | 25   |
| Sand                   | 50   |
| Shale & shells         | 370  |
| Hard pan               | 400  |
| Shale & shells         | 900  |
| Sand                   | 950  |
| Shale & shells         | 1160 |
| Sandy shale            | 1300 |
| Sandy shale & shells   | 1370 |
| Shale, lime, Anhydrite | 1405 |
| Shale, Anhydrite       | 1450 |
| Redbed                 | 1735 |
| Shale & shells         | 1915 |
| Shale                  | 2010 |
| Lime                   | 2215 |
| Shale & lime           | 2380 |
| Lime                   | 2465 |
| Lime & shale           | 3010 |
| Lime                   | 3180 |
| Lime & shale           | 3285 |
| Lime                   | 3440 |
| Hard lime              | 3465 |
| Lime                   | 3545 |
| Lime, shale, chert     | 3620 |
| Cherty conglomerate    | 3740 |
| Lime                   | 3765 |
| Total Depth            |      |

Tops:

|                        |      |
|------------------------|------|
| Topeka                 | 3186 |
| Heebner                | 3412 |
| Toronto                | 3431 |
| Lansing                | 3453 |
| B. Pennsylvania Congl. | 3706 |
| Simpson                | 3753 |
| Arbuckle               | 3763 |