


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BRIDGEPORT OIL CO., INC.
Farm - Hinkhouse No. 1.

SEC. 14 T. 9 N. 21 W
S E₄ NW

Total Depth. 3709'
Comm. 7-3-44 Comp. 8-4-44
Shot or Treated.
Contractor.
Issued. 8-19-44

County. Graham
KANSAS



Rotary O-3703
Cable 3703-09
CASING:
8 5/8" 212' Cem.
5 1/2" 3701' Cem.

Elevation. _____

Production. DDIC Pot. 31,560 B.

Figures Indicate Bottom of Formations.

surface & rock	60
sand & shells	105
sand & shale	212
shale & shells blue	700
shale	1103
sand	1420
sandy shale	1525
red bed & Pyrite	1670
shale	1675
Anhydrite	1719
lime	1826
shale & shells-lime	1930
shale	2105
shale & lime shells	2205
lime & shale	2331
shale & Pyrite	2405
shale & lime	2502
lime & shale	2538
lime broken	2620
lime & shale	2819
lime	2850
shale	2995
lime & shale	3086
sandy lime	3157
shale (stick y)	3192
lime & shale	3325
lime broken	3368
lime & shale	3420
lime	3576
lime & shale	3600
lime	3667
Conglomerate	3703
Arbuckle	3709
Total Depth	

FORMATION TOPS-DF:

Anhydrite	1675
Heebner	3360
Toronto	3385
Base Oread	3395
Lansing	3400
Base K.C.	3620
Penna. Basal Congl	3667
Simpson	3680
Arbuckle	3702

Swabbed 498 Bbls. in 24-hrs.
swabbing 2000' off bottom.
Draw-down potential--Indicat-
ed capacity 31,560 Bbls.-
Gravity 29.8 @ 93°