


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company - BRIDGEPORT OIL CO., INC.  
Farm - Hinkhouse No. 2.

SEC. 14 T. 9 R. 21 W  
SE NE NW

Total Depth. 3695'  
Comm. 8-7-44 Comp. 9-6-44  
Shot or Treated.  
Contractor.  
Issued. 9-23-44

County. Graham  
KANSAS



CASING:  
8 5/8"  
5 1/2"

Rotary O-3692  
Cable 3692-95  
215' Cem.  
3691' Cem.

Elevation. \_\_\_\_\_

Production. DD Pot. 4591 B.  
No wtr

Figures Indicate Bottom of Formations.

clay, sand & shale	0-215
shale & shells	660
shale	771
Dakota sand	1370
Dakota sand & shale	1560
shale & shells	1673
anhydrite	1715
shale & pyrite	1869
shale	2045
shale & pyrite shells	2165
shale, pyrite & lime	2270
shale & lime shells	2360
pyrite & shale	2405
shale & lime shells	2503
lime & shale	2551
shale & lime shells	2639
lime & shale	2928
shale & shells	3015
lime & shale	3074
shale	3145
lime	3272
lime & shale	3330
lime	3440
lime & shale	3493
K.C. lime	3520
lime	3581
lime & shale	3672
shale & congl	3692
lime & shale	3695
Total Depth	

Form. Tops DF:	
Heebner	3356
Toronto	3382
Lansing	3399
Congl	3671
Simpson	3673
Arbuckle	3691

Drlg plug-hole filled 640' Oil in 1 hr.  
1080' in 2 hrs.  
1390' in 4 hrs.  
2130' in 7 hrs.

Swabbed 163 Bbls. in 8 hrs. including head.  
3695' - 3698' Dolomite 2840' oil in 6 1/2 hrs.  
3698' - 3699' Dolomite, Fine grained gry  
3699' - 3701' Dolomite, Brwn, coarser  
2840' Oil in hole.

Swabbed 31 Bbls. PH for 12 hrs. 1400'  
off bottom.

Acidized w/500 gals.  
Draw down pot. 4591 Bbls. Oil - no wtr.  
Gravity 28.4 corr. to 60°.