


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CONTINENTAL OIL CO.
Farm - A. Morel No. 4.

SEC. 14 T. 9 R. 21 W
S E NW SW
990'S 990'E W $\frac{1}{4}$ Cor.

Total Depth. 3771' (DFL 3770)
Comm. 8-17-44 Comp. 9-12-44
Shot or Treated.
Contractor.
Issued. 12-2-44

County. Graham
KANSAS



CASING:
10 $\frac{3}{4}$ " 240' Cem.
6" 3765' Cem.

Elevation. _____

Production. Max. Pot. 3000 B. Echo.

Figures Indicate Bottom of Formations.

sand & shale	0-80
sand & shells	250
shale & sand	525
shale, lime & shells	1035
shale & shells	1110
sand & shale	1420
sand	1430
shale & shells	1715
anhydrite	1780
red bed & shale	1830
shale & lime	2120
shale & shells	2260
lime & shale	2420
lime brkn	2450
shale & shells	2550
lime	2565
lime & shale	2760
lime brkn	2855
lime	2905
lime brkn	3060
lime	3085
lime brkn	3250
lime	3723
chert	3746
dolomite sdy	3757
lime	3771
Total Depth	

DFL 3770

Top of Arbuckle Lime 3764

9-7-44 Drilled out c.m. - hole
filled 2800' w/oil
9-8-44 Swabbed 57 BOPH, no wtr,
for 3 hrs off btm
9-12-44 Established a maximum
3000 BO Echometer potential

Total Depth 3770 in Arbuckle Lime

Note: Footages calculated from
pumping derrick floor level,
except formations