


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

CONTINENTAL OIL CO.
J. Morel No. 2.

SEC. 15 T. 9 R. 21 W
NWc SE
330'S 330'E Center

Total Depth. 3710' (GL 3706)
Comm. 12-29-42 Comp. 1-21-43
Shot or Treated.
Contractor.
Issued. 7-17-43

County. Graham



CASING:
10⁵/₈" 239' Cem.
7" 3687' Cem.

Elevation.

Production. Echo. Pot. 3000 B.
No wtr, Max.

Figures Indicate Bottom of Formations.

surface clay	0-30
shale & sand	150
shale blue & shells	262
shale & shells	600
sand	697
shale & shells	800
sand	900
shale & sand	1145
shale	1180
sand & shale	1660
lime	1705
shale & shells	2460
shale & lime	2525
shale & lime shells	2775
lime	2805
shale & lime	3080
shale	3110
lime & shale strks	3160
shale & lime	3205
lime	3215
shale	3250
lime	3290
brkn lime & shale	3320
shale	3335
lime K.C.	3495
lime & shale strks	3565
shale & lime	3650
lime cherty	3680
cong. & lime strks	3699
lime	3710

Total Depth.
(TD from Gr. Lev. 3706)

1-15-43 drld cement plug and
hole filled 2800' w/oil in 30
minutes

1-26-43 Estb. a Max. Allowed
Echo. Pot. of 3000 BO, no wtr

Top Arbuckle lime 3677

Note: Above footages calculated
from ground level except
formation record which is from
top of rotary table