


CONTINENTAL OIL CO.
Drumm Commission Co. No. 1,SEC. 16 T. 9 R. 21W
SEc NE
330'N 330'W E $\frac{1}{4}$ Cor.Total Depth. 3702'
Comm. 1-6-39 Comp. 1-31-39
Shot or Treated. 1000 & 4000 Gals.
Contractor.
Issued. 4-8-39

County. Graham

CASING:
13" 241'
95/8" 1494'
6" 3680'

Elevation.

Production. Pot. 1043 B.
No wtr.

Figures Indicate Bottom of Formations.

cellar	11	brkn limo	3135
surface clay	50	limo	3160
sand	95	brkn limo	3170
blk shale & shells	510	sdv limo sft	3180
brown shale & shells	600	limo	3207
shale & shells	787	limo sft	3214
shale, red rock, sand	890	limo	3260
sand hrd	920	limo sft	3266
red rock, shale	960	limo brkn & shale	3295
shale blue	985	limo sft	3305
sand	1087	limo	3314
shale blue	1160	brkn sdv limo	3323
sand	1315	limo	3378
shale	1340	limo & shale	3390
sand	1375	limo Kansas City	3401
shale	1395	limo sft	3408
shale blue	1440	limo	3540
packed sand	1455	limo & shale	3560
red rock & shale	1525	limo sft (oil sh)	3568
red rock & shale w/ pyrite	1600	limo (oil sh)	3610
red rock & pyrite	1661	limo	3618
anhydrite	1712	limo brkn & red shale	3640
brkn limo, anhydrite & red bed	1735	limo & shale	3680
red bed & shells	1776	chert & conglomerate	3685
red bed & shale	1791	Arbuckle	3695
shale, red rock, & shell	1830	limo	3702
red bed	1870	Total Depth.	
shale & shells	1957	Top Topeka limo	3180
shale & lime brkn	2050	Top Lansing limo	3400
limo	2073	Top Arbuckle limo	3679
brkn limo & shale	2090		
shale brown & blue	2123		
white lime & shale	2152	Hole filled up 700' w/oil in eight hours.	
shale & shells	2195	Well acidized 2-1-39 w/ 1000 Gals.	
brkn limo & shale	2245	Well pumped 149 BO 8 $\frac{1}{2}$ hrs, pumping 101 BO 1st 5 hrs and 48 B. last 3 $\frac{1}{2}$ hrs.	
limo	2260	Well acidized second time 2-19-39 w/4000 Gals.	
brkn limo & shale	2289	2-21-39 on initial potential test the well pumped 347.55 BO 8 hrs, giving the well a 24-hr potential of 1043 B. oil, no wtr.	
shale red & blue	2342	Gravity of oil 27.3 corrected	
lime brown	2360		
lime & blue shale	2385		
blk shale & lime shells	2435		
lime & shale	2462		
shale & lime brkn	2562		
lime & shale	2646		
shale	2650		
lime white sft	2658		
lime brown	2670		
shale & lime	2692		
shale & lime brkn	2740		
lime & shale	2775		
shale & shells	2970		
limo	3005		
brkn limo & shale	3016		
limo & shale	3078		
shale	3105		
limo	3110		