


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

Company - CITIES SERVICE OIL CO.
Farm - Seefeld No. 2

SEC. 18 T. 9 R. 21
NW SE NE
990' N. & 990' W. of E/4
corner

Total Depth. 3793
Comm. 5-14-50 Comp. 5-30-50
Shot or Treated.
Contractor. R. W. Rine Drlg.
Issued. 7-8-50

County. Graham
KANSAS



Elevation. 2277 Ind.

Production. D.D. pot. 1620 oil,
nowtr.

CASING:

8 5/8" 240' cem. w/150 sx.
5 1/2" 3780' cem. w/175 sx.

Figures Indicate Bottom of Formations.

surface clay & sand	105
shale & sand	240
shale & shells	945
shale & sand	1600
shale & shells	1760
anhyd.	1805
shale & shells	2230
lime	2460
shale & lime	2550
lime & shale	2685
lime	2825
lime & shale	3325
lime	3371
lime & shale	3450
lime	3545
shale & lime	3595
lime	3685
lime & shale	3735
lime	3780
3780 = 3780 SLM	
lime	3793
Total Depth	

Tops:

Lansing	3486
Congl.	3754
Simpson	3774
Arbuckle	3778

Pen. 15'

Fullup:

60' oil in 1 hr. 10 mns.	3790 1/2
285' oil in 3 hrs.	3790 1/2
1990' oil in 6 hrs.	3793
2660' oil in 6 1/2 hrs.	3793
2543' oil in 7 1/4 hrs.	3793
2650' oil in 7 3/4 hrs.	3793
2808' oil in 9 1/4 hrs.	3793