

15-065-01431

## KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL COMPANY

SEC. 18 T. 9 R. 21W

FARM Seefeld

NO. 5

LOC. SE NE NE

990' S. &amp; 330' W. of NE cor.

TOTAL DEPTH 3784

COMM. 10-18-50

COMP. 11-1-50


SHOT OR TREATED

CONTRACTOR R. W. Rine Drlg. Co.

ISSUED 1-13-51

COUNTY Graham

KANSAS



## CASING

8 5/8" 240' cem. w/175 sx  
 5 1/2" 3779' cem. w/175 sx

ELEVATION 2269

PRODUCTION D.D.Pot. 3000 oil &  
 no. wtr. Ind. cap.  
 3488 bbls. per day

## FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay & lime 240  
 shale, sand & shells 1765  
 anhydrite 1800  
 shale & shells 2070  
 shale, shells & lime 3100  
 lime & shale 3335  
 lime 3770  
 shale & chert 3774  
 sand 3776  
 lime 3778  
 3778 RTD = 3780 SLM  
 lime 3784

Total depth

## Tops:

Lansing (Corr.) 3474  
 Cherty Congl. (Corr.) 3753  
 Arbuckle (Corr.) 3778  
 Penetration 6'  
 Total depth 3784

## Fillup:

70' oil in 15 mins. at 3781  
 100' oil in 40 mins. at 3781  
 1600' oil in 1 hr. 40 mins. at 3784  
 2134' oil in 2 hrs. 10 mins. at 3784  
 2466' oil in 2 hrs. 40 mins. at 3784  
 2810' oil in 4 hrs. 40 mins. at 3784  
 7 7/8" rotary hole  
 Elev. 2267 Gr.