

15-065-01432

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 18 **T.** 9 **R.** 21W

FARM Seefeld

NO. 6

LOC. NW SW NE

990' N, 330' E of center

TOTAL DEPTH 3843 SLM

COMM. 11-8-50


COMP. 11-16-50

SHOT OR TREATED

CONTRACTOR R. W. Rine Drlg Co.

ISSUED 1-20-51

COUNTY Graham



CASING

8 5/8" 240' cem w/175 sx.

5 1/2" 3840' cem w/175 sx.

ELEVATION 2308 (2305 GR)

PRODUCTION Phy. 167 bbls,
26% wtr

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay 40
sand, lime 240
shale, sand, shells 1810
anhydrite 1845
shale, shells 2685
lime, shale 3545
lime 3810
lime, chert 3841
lime, chert 3841
3841 RTD = 3843 SLM
Total Depth

Tops: Corr.
Lansing 3527
Conglomerate 3811
Simpson Sand 3828
Simpson Shale 3830
Arbuckle 3838
Penetration 5

Fillup:

150' oil in 35 mins.
410' oil in 1 1/4 hrs.
740' oil in 1 hr. 50 mins.
1560' oil in 3 1/2 hrs.
1860' oil in 4 hrs. 35 mins.
2805' oil in 15 hrs.

Drill Stem Test: 3837-41,
recovered 430' oil and 30'
oil-cut mud in 30 mins.,
BHP 1040#.

7 7/8" rotary hole.