

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E Murdock Wichita, Kansas


Company - PEEL HARDMAN, N. APPLEMAN, COPPINGER
Farm - Sut or "B" No. 1

SEC. 18 T. 9 R. 21W
SE SE SE

Total Depth. 3840'
Comm. 12-5-49 Comp. 12-31-49
Shot or Treated.
Contractor. Glenn Pool Drilling Co
Issued. 2-18-50

County. Graham

KANSAS



Elevation. 2301 Ind.

Production. 3000 bbls

CASING:

8 5/8" 142' cem
5 1/2" 3829' cem

Figures Indicate Bottom of Formations.

surface clay & sand	35
sand	70
shells and shale	110
shale and shells	450
shale shells and sand	1110
shale and shells	1300
sand	1470
shale and shells	1780
anhydrite	1825
shale and shells	2200
lime and shale	2380
lime	2530
bkn lime	2705
lime	2850
lime and shale	3254
lime	3820
lime and shale	3838
lime	3840
Total Depth	

CABLE TOOL DATA:

1-7-50 Rigging up. Bailing mud. Preparing to mix mud.
1-8-50 Mixing mud. Bailing & swabbing mud. Cleaned out to bottom. Drilled cement. Swabbing
1-9-50 Swabbing & testing. Preparing to run tubing.
1-10-50 Running tubing and rods. Tearing down.

Tops: Schlumberger

Anhydrite	1782
Base	1823
Heebner	3472
Lansing	3493
Lansing K. C.	3510
Arbuckle	3823