

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
805 East <sup>W</sup>urdock, Wichita, Kansas


15-065-01012

Company - CITIES SERVICE OIL CO.  
Farm - Fury "A" No. 2

SEC. 20 T. 9 R.21W  
NW NW NE  
330' S and 330' E of N/4 Cor.

Total Depth. 3812  
Comm. 6-21-50 Comp. 7-12-50  
Shot or Treated.  
Contractor. R.W.Rine Drilling Co.  
Issued. 9-2-50

County. Graham  
KANSAS



Elevation. 2297

Production. D.D. Pot.2770 B.O.

CASING:

8 5/8" 240' cem w/175 sx.  
5 1/2" 3805' cem w/175 sx.

Figures Indicate Bottom of Formations.

clay, sand 180  
shale, sand 240  
shale, shells 1175  
sand, shale, shells 1725  
shale 1775  
anhydrite 1811  
shale, shells 2120  
shale, lime 2365  
shale, broken lime 2475  
lime 2750  
lime, shale 3425  
lime 3750  
lime, shale 3785  
lime 3805  
3805 RTD = 3805SLM  
lime 3812  
Total Depth

Tops:  
Lansing 3500  
Eros. Arbuckle 3803  
Arbuckle 3804  
Penetration 8

Fillup: 320' oil in 15 mins. at 3806  
1760' oil in 1 hr.20 min. 3809  
2310' oil in 1 hr.50 min. 3809  
2565' oil in 2 hrs.20 min. 3809  
2720' oil in 2 hrs.50 min. 3809  
2830' oil in 3 hrs.50 min. 3809

7-11-50 Physical potential 480 oil, no  
water in 24 hrs.