

15-065-01463

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL COMPANY

SEC. 22 T. 9 R. 21W

FARM Darnell

NO. 6

LOC. SW NW NW

990' S, 990' E of NW corner

TOTAL DEPTH 3770

COMM. 9-27-50

COMP. 10-11-50


SHOT OR TREATED

CONTRACTOR R. W. Rine Drilling Co.

ISSUED 12-9-50

COUNTY Graham

KANSAS



CASING

8 5/8" 275' cem. w/175 sx
 5 1/2" 3767' cem. w/175 sx
 (Cem. 1765' to surface w/550 sx)

ELEVATION 2262

PRODUCTION Phy.Pot. 31 oil,
 90% wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, shells, shale 280
 sand, shale & shells 1735
 Anhydrite 1775
 Shale & shells 2290
 shale, shells & lime 3095
 lime & shale 3360
 lime 3768
 3768 RTD = 3769 SIM
 lime 3770
 Total depth

Tops:

Lansing Corr. 3465
 Cherty Cong. " 3752
 Simpson " 3754
 Arbuckle " 3764
 Penetration 6'

Elevation 2260 Ground

Fillup 140' fluid in 40 mins.
 360' fluid in 1 hr. 10 mins.
 1500' fluid in 6 hrs. 10 mins.
 241' oil & 2060' wtr in 16 hrs.
 10 mins.

10-16-50: Pumped 33 Oil & 114 wtr. 24
 hrs.
 7 7/8" rotary hole.