


CITIES SERVICE OIL CO.
Morel "B" No. 1.

SEC. 22 T. 9 R. 21 W.
NE SE NE
1370'S 330' W of NE cor.

15-065-01464

Total Depth. 3777
Comm. 11-24-41 Comp. 12-13-41
Shot or Treated. none
Contractor. Hissom Drilling Co.
Issued. 1-31-42

County Graham.



CASING.

85/8" 210' cemented.
5 1/2" 3775' cemented.

Elevation.

Echometer
Production. Pot. 3000 B.O.

Figures Indicate Bottom of Formations no wtr. Ind. Cap. 15,890 B.

surface sand	110
shale and shells	210
shale	538
shale shells and sand	1104
sand	1137
lime shells	1139
shale and shells	1290
sand	1400
red bed shale & shells	1500
shale and lime	1653
shale red	1718
anhydrite	1761
shale and shells	2025
shale	2126
shale and shells	2188
broken lime	2260
lime	2268
broken lime	2300
shale and lime shells	2397
shale and lime broken	2430
lime	2500
broken lime	2650
shale and lime	2806
lime	2853
sd lime	2874
lime	2946
shale	3054
lime and shale	3215
shale	3283
lime	3702
lime and shale broken	3736
lime	3753
shale	3779
lime	3780

3780 Rot. T. D. = 3775 SLM
dolomite 3777

Total Depth.

Corr. Top Arbuckle 3774
Penetration 3'

Fillup 2950' Oil in 45 min.