

15-065-01470

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

SEC. 22 T. 9 R. 21W

FARM Morel "B"

NO. 7

LOC. SE SE NE

330' N, 330' W of E/4 cor.

TOTAL DEPTH

3786

COMM.

11-26-50

COMP. 12-21-50

SHOT OR TREATED

CONTRACTOR


R. W. Rine Drlg Co.

ISSUED

1-20-51

COUNTY Graham

KANSAS



CASING

8 5/8" 240' cem w/175 sx.

5 1/2" 3782' cem w/175 sx.

and from 1748' to surface w/600 sx.

ELEVATION 2290 (2288 Gr.)

PRODUCTION Draw-Down Pot.
2799 bbls oil, 5% water.

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, shale &
 shells 0-1740
 anhydrite 1775
 shale, shells 2240
 shells, shale, lime 2465
 shale, lime 2595
 lime 2745
 lime, shale 3405
 lime 3720
 shale, lime 3780
 3780 RTD= 3783 SLM
 lime 3783
 Total Depth

Tops: Corr.

Lansing 3488

Arbuckle 3781

Penetration 5

Fillup:

685' oil in 20 mins.

1435' oil in 50 mins.

1921' oil in 1 hr. 20 mins.

2460' oil in 2 hrs. 20 mins.

2600' oil in 3 hrs. 20 mins.

2731' oil in 9 hrs. 20 mins.

7 7/8" rotary hole.