


Company - CONTINENTAL OIL CO.
Farm - Putnam Investment Co. "A" No. 3.

SEC. 23 T. 9 R. 21 W
NW SE NW
8 90' N 990' W Center

Total Depth. 3816' (CFL 3814)
Comm. 2-25-44 Comp. 3-26-44
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 8-5-44

County. Graham
KANSAS



CASING:

10^{3/4}" 239' Cem.
6" 3808' Cem.

Elevation. _____

Production. Pot. 602 B., Phy.

Figures Indicate Bottom of Formations.

surface soil	40
shale & shells	605
shale & sand	985
shale & shells	1090
shells & sand	1261
sand & shale	1501
shale & shells	1745
anhydrite	1798
shale & lime shells	1840
shale	1890
shale & shells	2280
lime & shale	2295
lime	2325
lime brkn & shale	2363
lime brkn	2470
lime	2510
lime brkn	2547
lime brkn & shale	2605
lime	2680
lime brkn	2775
shale & lime	2836
lime	2900
shale	2920
lime & shale	2964
lime brkn	3069
lime brkn & shale	3112
lime brkn	3129
lime & shale	3179
lime bro	3212
lime	3407
lime bro & shale	3474
lime	3772
shale	3794
chert	3805
lime	3816
Total Depth.	

Top of Arbuckle Lime 3807

4-15-44 Drilled cement plug &
Hole filled 1800' w/oil in 4 hrs.
4-29-44 Established a 24 hr Phy
Pot. of 602 Bbls. Oil

Total Depth in Arbuckle Lime 3814

Note:

Footages fm cement floor level,
except formations.