

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company-SKELLY OIL CO.
Farm- Flora Barry

No. 2

SEC. 24 T. 9 R. 21W
SE NE SE
990' fr NL & 330' fr EL
of SE
County. Graham

Total Depth. 3835

Comm. 5-17-49

Comp. 6-1-49

Shot or Treated. acid

Contractor. Claude Wentworth Drlg. Co.

Issued. 9-17-49

KANSAS



Elevation. _____

Production. Dry

CASING:

8 5/8" OD 299' cem. w/150 sx.

5 1/2" OD 3827' cem. w/200 sx.

Figures Indicate Bottom of Formations.

surface soil &	
sand	10
sand	100
sand & gravel	200
sand, shells &	
sand rock	300
Drilled 12 1/4" hole.	
shale	625
shale & sand	680
shale	935
sand	1300
sand & red bed	1755
anhyd.	1305
shale	1340
shale & lime	
shells	2045
shale	2200
shale & lime	2595
shale	2640
lime & shale	3794
congl.	3814
shale	3826
dolo. fine to med.	
xyl.	3829
dolo. fine to coarse	
xyl.	3835
Total Depth	

Tops:

Heebner shale	3488
Toronto lime	3514
Lansing lime	3528
Congl.	3794
Simpson shale	3814
Arbuckle lime	3826

Fair por. & saturation 3826-3829

Poor to fair por. & sat. 3829-3835

6-21-49 1st acid treatment:

300 qts.- 3823-3827

6-26-49 2nd acid treatment:

250 qts. 3823-3827

7-2-49 3rd acid treatment:

300 qts. 3823-3826

By Dowell Inc.