


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company - B & R DRILLING, INC.  
Farm - Cox No. 1

SEC. 26 T. 9 R. 21W  
NE NW NW

Total Depth. 3835  
Comm. 10-6-48 Comp. 10-19-48  
Shot or Treated.  
Contractor.  
Issued. 1-21-50

County. Graham  
KANSAS



Elevation. 2322 *ft*

Production. Pot. 140 bbls.

CASING:  
8 5/8" 282' cem w/165 sx.  
5 1/2" 3831' cem w/100 sx.

Figures Indicate Bottom of Formations.

clay	36
sand, shale	60
shale	75
sand	100
shale, shells	147
sand	180
shale, sand	265
shale, shells	525
sand	585
shale, shells	900
sand, shale, shells	1140
sand	1195
shale	1225
sand, shale	1480
shale, shells	1590
red bed, shale	1773
anhydrite	1812
shale	2045
lime, shale	3115
lime	3205
lime, shale	3435
lime	3831
Arbuckle	3835
Total Depth	

Top:	
Lansing K. C.	3532
Arbuckle	3831