


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - B & R DRILLING COMPANY
Farm - Cox No. 2

SEC. 26 T. 9 R. 21W
NW NE NT

Total Depth. 3816
Comm. 11-22-48 Comp. 12-6-48
Shot or Treated.
Contractor.
Issued. 2-5-49

County. Graham
KANSAS



Elevation. 2297 *ft.*

Production. 84 bbls.

CASING:

8 5/8" 187' cem w/100 sx.
5 1/2" 3813' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay 40
sand, shale 70
sand 90
shale, shells 125
sand 160
shale, sand, shells 187
shale, shells 520
sand 585
shale, shells 870
sand, shale, shells 1090
shale, shells 1260
sand 1580
shale, shell 1665
shale, redbed, shells 1755
anhydrite 1794
shale, shells 1980
shale, lime shell 2165
lime, shale 2710
lime 2755
lime, shale 3500
lime 3816
total depth

Tops:

Lansing/K.C. 3502
Arbuckle 3813