

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

15-065-01141

Company- WESTGATE-GREENLAND OIL CO.
Farm- Smith "A" No. 1

SEC. 31 T. 9 R.21W
S. S. SE

Total Depth. 3885 R.B.

Comm. 1-3-52


Comp. 1-24-52

Shot or Treated.

Contractor. Jackson Drlg.

Issued. 4-5-52

County Graham
KANSAS



Elevation. 2510 D.F.

Production. 25 bbls. temp.

CASING:

8 5/8" 211' cem. w/150 sx.
5 1/2" 3881' cem. w/100 sx.

Figures Indicate Bottom of Formations.

sand & soil	75
shale	185
shale & shells	211
sand & shale	300
shale & shells	900
sand	1090
shale & shells	1350
shale	1525
red bed & shells	1630
shale & shells	1780
anhyd., lime & sand	1815
shale & shells	1905
shale	2200
shale & shells	2260
lime & shale	2370
lime	2410
lime & shale	2620
lime	2630
lime & shale	2830
lime	2900
lime & shale	3020
lime	3075
lime & shale	3460
lime	3500
lime & shale	3534
lime	3760
shale	3773
shale & lime	3823
chert, shale & lime	3856
sand & shale	3882
arb. lime	3885
Total Depth R.B.	

Tops:

Anhyd.	1780
Reebner	3494
Dodge	3515
Mansing	3532
Base L.C.	3758
Wernaton	3812
Simpson	3860
arb.	3880

No Schlumberger, no tests made in Arb.
C.O. to bottom, filled up 1600 oil in 2 hrs.
2600' in 5 hrs., no wtr. bailed 10 bbls.
in 2 hrs.

D.S.T. 3558-84, open 1/2 hr. rec. 180'
salt wtr. BHP 1300#, blur press. 180#.
3600-30 open 1/2 hr. rec 20' sl.
oil & gas cut mud. No BHP
3716-36, open 1/2 hr., rec 8' mud, BHP 300#.