


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HERMAN GEORGE KAISER, OIL PRODUCER SEC. 33 T. 9 R.21W
Farm- Bragg No. 9 NW NE SE

Total Depth. 4314
Comm. 5-11-55 Comp. 5-28-55
Shot or Treated.
Contractor. H-30, Inc.
Issued. 7-23-55

County Graham
KANSAS



Elevation. 2312 FB

Production. Dry

CASING:

8 5/8 189'
5 1/2 3990'

Figures indicate Bottom of Formations

surface clay & sand	120
sand & shale	160
shale	720
sand	760
shale	905
shale w/ sand streaks	1230
shale & shells	1290
sand	1550
shale, shells & red bed	1785
anhydrite	1825
red bed, shale & shells	1925
shale & shells	2100
shale, shells & salt	2270
shale & shells	2385
shale & lime	2825
shale & sandy lime	2920
shale & lime	3520
lime	3780
lime & shale	3899
lime; shale, chert & iron	3940
lime, chert & iron	3970
lime & chert	4100
lime, chert & iron	4131
lime & chert	4144
lime	4190
lime & chert	4230
lime	4306
lime & chert	4314
Total Depth	

TOPS:	
Heebner	3509
Toronto	3533
Lansing	3550
Base KC	3774
Marmaton	3835
Cherty conglomerate	3882
Conglomerate sand	3893
Arbuckle	3930