


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - DERBY OIL CO. & GLENN W. PEEL
Farm Miller No. 1.

SEC. 27 T. 9 R. 21 W
NWc NW

Total Depth. 3843
Comm. 1-3-46 Comp. 2-16-46
Shot or Treated.
Contractor. Glenn W. Peel
Issued. 3-2-46

County. Graham
KANSAS



CASING:
10 1/2" 394' 10" Cem.
5 1/2" 3833' Cem.

Elevation. 2922 rb

Production. S.W.D.

Figures Indicate Bottom of Formations.

shale & shells	0-298
shale	1090
shale	1244
sand & shale	1485
shale & shells	1585
shale	1750
anhydrite	1795
shale & shells	2480
shale & lime	2585
lime	2615
lime brkn & shale	2640
lime	2675
shale & lime	2805
shale & lime brkn	2865
lime brkn	2920
shale & shells	3115
shale & lime	3175
shale	3190
lime brkn	3250
shale & lime brkn	3340
lime & shale	3470
lime	3720
lime & shale	3772
lime	3843
Total Depth	

Geological Survey

Tops:

Anhydrite	1715
Lansing	3494
Base Kans. City	3740
Arbuckle	3830

DST Packer @ 3833 open
30 min. rec. 6' mud
no wtr.; DP DD 3838
no show Perf. 36/3832-
38 no show; 500A 1400#
Press for 3 1/2 hrs. Would
not take; DD 3841 no
show oil or wtr. DD 3843
TD HFW. Dumped 4 sacks
cement on bottom to
hold for SWD.