

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-065-20092

COMPANY RAYMOND OIL

SEC. 9 T. 9 R. 22W
 100' NW NW SE SE

FARM Rice Estate

NO. 1

TOTAL DEPTH 3919'

COMM. 9-27-67

COMP. 10-7-67


SHOT OR TREATED

CONTRACTOR Raymond Oil

ISSUED 12-30-67

COUNTY Graham

KANSAS



CASING

20	10	
15	8 5/8"	225' cem w/ 175 sx
12	6	
13	5 1/2"	3918' cem w/ 150 sx

ELEVATION 2294' KB

PRODUCTION 98 BOPD PLUS 4%W
 Lans 3737 1/2 - 42 1/2 Grav 27.1

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Shale	75
Shale & Sand	228
Shale & Shells	1396
Sand & Shale	1600
Shale & Lime	1758
Lime	1882
Red Bed & Shale	2035
Shale & Shells	2270
Shale w/Lime	2242
Lime & Shale	3614
Lime	3753
Lime, Shale & Chert	3919
RTD	3919



FORMATION TOPS

		Log
Anhydrite	1846	1848
Base Anhydrite	1879	1882
Topeka Ls.	3292	
Heebner Sh.	3505	3505
Toronto Ls.	3530	3549
Lansing Ls.	3549	
Base Kansas City	3760	3760
Conglomerate Chert	3896	3896
Arbuckle Dolomite	3917	3917
TD	3919	

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

I hereby certify that the above and foregoing is true and correct to the best of my knowledge.

Wm H Raymond