

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-005-02260


Company- ANDERSON-PRICHARD OIL CORP.
 Farm- Buss "C" No. 4

SEC. 13 T. 9
 SE SW NE

R.22W

Total Depth. 3807
 Comm. 9-28-51 Comp. 10-9-51
 Shot or Treated.
 Contractor. Glenn W. Peel
 Issued. 11-10-51

County Graham
 KANSAS



CASING:

8 5/8" 262'
 5 1/2" 3804'

Elevation. 2280 RB
 Production. dry 2277 (m)

Figures Indicate Bottom of Formations.

surface clay	252
shale	900
sand, shale	1225
shale	1310
shale, shells	1665
anhydrite	1700
shale	1990
shale, lime	2330
lime	2545
lime, shale	3350
lime	3695
lime, shale	3755
lime	3790
lime, shale	3804
lime	3807 RTD
Total depth	

Tops:
 Anhydrite 1763
 Topeka 3356
 Heebner 3451
 Lansing 3490
 Arbuckle 3803

Drld Plug & CO to bottom,
 Bailed 3/4 BOPH, No wtr. in
 7 hrs. Az w/250 gal. Max Press.
 450#, min. press. 50#. Swbd
 off load wtr & acid, 2 hr. swab
 test: 1 BOPH & 40 BWPH, 3 hr
 swab test: 3/4 BOPH & 25 BWPH,
 Static fluid level 1150' from
 surface. Analysis shows wtr.
 to be from Arbuckle form, 11
 hr. swab test: 2 BOPH & 50 BWPH.
 Squeezed open hole w/cem. Perf.
 3799-3804 w/4 jet shots per ft.
 Bailed 7 GW & 1 BOPH/5 hrs.
 Perf. 3804-05 w/9 jet shots.
 Az w/250 gal. Max. Press. 700#
 Went in on vacuum, Swb 40 BW &
 1 1/2 BOPH/5 hrs.