

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-DUG-01520

Company- ANDERSON-PRICHARD OIL CORP.
Farm- Buss "D" No. 1

SEC. 13 T. 9 R. 22W
NE NE SE

Total Depth. 3797
Comm. 8-1-51 Comp. 8-12-51
Shot or Treated.
Contractor. Glenn W. Peol
Issued. 10-6-51

County Graham
KANSAS



CASING:

8 5/8" 257' cem
5 1/2" 3796' cem

Elevation. 2284 RB
2281 (2nd)

Production. 144 BOPD, no water
State Test

Figures indicate Bottom of Formations.

shale	40
shale, sand	680
shale, shells	1185
sand, shale	1660
shale	1735
pyrite	1770 ✓
shale, shells	1995
shale	2030
shale, shells	2055
shale	2210
shale, shells	2300
shale	2340
lime, shale	2855
lime	3055
lime, shale	3395
lime	3797 RTD
Total Depth	

Tops:	
Heebner	3447
Lansing	3486
Arbuckle	3795

DST 3480-3545. Open 30 min.
Good blow. Rec. 734' slightly
gas cut salt water w/specks of
free oil throughout and 3' of
free oil in tool. BHP 1150#.
R.P. 280#/15 min.

DP & CO to bottom. Swab 7 1/2 BO
✓ .4% B.S./1 hr.
Swab 7 BOPH/16 hrs w/trace of
BS, no wtr. POP
9-10-51 P 90 BO ✓ .4% wtr 15 hrs.
9-11-51 P 115 BO ✓ .4% wtr 24 hrs.
9-13-51 State Test: 144 BOPD, no
water.