

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

500 East Murdock,

Wichita, Kansas

Company- ANDERSON-PRICHARD OIL CORP.
 Farm- Buss "D" No. 2

SEC. 13

T. 9


R. 22W

SW NE SE

15-065-01521

Total Depth. 3802
 Comm. 8-15-51 Comp. 8-24-51
 Shot or Treated.
 Contractor. Glenn W. Peel
 issued. 10-6-51

County Graham
 KANSAS



CASING:

8 5/8" 248' cem
 5 1/2" 3800' cem.

Elevation. 2278 RB
 2275 (m)

Production. 143 bbls, no wtr.
 State Prod. Test.

Figures Indicate Bottom of Formations.

clay, sand 250
 shale 350
 shale, shells 615
 sand 935
 shale, shells 1250
 sand, shale 1400
 shale 1790
 anhydrite 1825
 shale 2040
 shale, shells 2280
 shale, lime 2645
 lime broken 2815
 lime, shale 3200
 lime 3435
 lime, shale 3465
 lime 3801
 Total Depth 3802 RTD

Tops:
 Heebner 3448
 Lansing 3488
 Arbuckle 3799

DST 3571-81. Open 25 min.
 Rec. 240' water & 650' drlg fluid.
 No BHP. Packer failed after 10min.

DP and swabbed 76 BO / .2% BS/13 hr test.
 Ran tubing & rods.
 9-8-51 p 49 BO / .4% wtr/16 hrs.
 9-13-51 State Productivity Test:
 143 BOFD, no water.