

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-01523

Company- PRODUCERS PIPE & SUPPLY COMPANY
Farm- Sandzen No. 1

SEC. 14 T. 9 R. 22W
NE SE SW

Total Depth. 3860'
Comm. 6-27-57 Comp. 7-13-57
Shot or Treated.
Contractor. Veeder Supply & Development Co.
Issued. 10-19-57

County Graham
KANSAS



CASING:
8 5/8" 237' cem w/140 sx
5 1/2" 3857'

Elevation. 2304' KB

Production. Pump 172 barrels
fluid, 18% water

Figures indicate Bottom of Formations.

rock	30
sand, shale	80
grey shale	237
shale	875
shale & sand	1585
shale, shells, red bed	1808
anhydrite	1850
shale & shells	2225
shale & lime strks	2375
lime & shale	3055
shale lime	3160
lime & shale	3295
shale lime	3365
lime	3570
lime chert	3588
lime	3860
Total Depth	RTD

TOPS: Electric Logs Run - None
Heebner 3483
Toronto 3510
Lansing 3523
Base Kansas City 3728
Marmaton Chert 3810
Arbuckle 3856

D.S.T. #1. 3515-3546 Open 1 hr. Rec. 700#.
75' SOC Muddy water. FP 35-50#. 15"
IBHSIP 70#. 15" FBHSIP 790#.

D.S.T. #2. 3546-3570 Open 1 hr. Rec.
270' gas, 30' SO&GCM, 60' MOCM, 30' HO&GCM,
90' Froggy MCO. FP 60-125#. 15" IBHSIP 770#.
750#. 15" FBHSIP 675#.

D.S.T. #3. 3569-3588 Open 1 hr. Rec.
15' SOCM. FP 0-0#. 20" IBHSIP 0#. 30"
FBHSIP 0#.

D.S.T. #4. 3586-3609 Open 1 hr. Rec.
90' gas, 30' SO&GCM, 60' HOCM, 30' Froggy
oil, 60' HMCO, 95' VHOCM. FP 0-93#. 20"
IBHSIP 697#. 30" FBHSIP 647#.

D.S.T. #5. 3646-3710 Open 1 hr. Rec.
45' SOCM. FP 0-0#. 20" IBHSIP 714#. 30"
FBHSIP 377#.

D.S.T. #6. 3705-3725 Open 1 hr. Rec.
40' SOCM. FP 55-55#. 20" IBHSIP 535#.
30" FBHSIP 1120#.

D.S.T. #7. 3846-3860 Open 1 hr. Rec.
25' MOCM. FP 0-0#. 20" IBHSIP 770#. 30"
FBHSIP 1090#.